

ADDENDUM NO. 1
LAKESHORE DRIVE BOAT DOCK FACILITIES
CITY OF CELINA, OHIO

Issuance Date: 4-9-09

BID DATE RESCHEDULED FOR APRIL 16, 2009 AT 11 AM

The following items are to clarify the construction documents for this project:

GENERAL NOTES AND CLARIFICATIONS:

- See the attached list of ODNR acceptable boat dock manufacturers.

SPECIFICATIONS:

Section 00300 – Bid Form

- See attached revised Bid Form.

DRAWINGS:

Sheet 5 of 8:

- Lean concrete is to be placed at the bottom and behind the pre-cast panels to prevent the base aggregate from being washed out. An approximate dimension of 3'x8' per panel is the engineers estimate.
- H-Beams should be 20lb/ft

**SECTION 00300 BID FORM
LAKESHORE DRIVE BOAT DOCK FACILITIES**

ITEM	UNIT OF	APPROX.	UNIT	TOTAL
NO. DESCRIPTION	MEASURE	QTY.	COST	COST
<u>BASE BID ITEMS</u>				
201 CLEARING AND GRUBBING	LUMP	1	_____	_____
203 ROCK EMBANKMENT ODOT UNGRADED TYPE A, AS PER PLAN	TON	100	_____	_____
203 ROCK EMBANKMENT ODOT TYPE D, AS PER PLAN	TON	525	_____	_____
203 ROCK EMBANKMENT ODOT #1 STONE	TON	300	_____	_____
205 ROCK EMBANKMENT ODOT # 2 STONE	TON	325	_____	_____
304 ROCK EMBANKMENT ODOT #57 STONE	TON	275	_____	_____
507 ADDITIONAL PILE LENGTHS	FT.	100	_____	_____
507 H-BEAM SPLICE FOR ADDITIONAL H-BEAM LENGTH	EACH	10	_____	_____
603 12" HDPE STORM SEWER	LF	30	_____	_____
608 6" CONCRETE WALK	S.F.	12500	_____	_____
SPEC SEAWALL CONSTRUCTION, AS PER PLAN	LF	450	_____	_____
(The unit price for seawall construction is to include the re-positioning of the existing rock, and installation of all deadman anchors, tie-rods, steel pilings, precast concrete panels, and wood trim).				
SPEC INSTALLATION OF NEW FIXED DOCKS	EACH	7	_____	_____
SPEC INSTALLATION OF NEW FLOATING DOCKS	EACH	2	_____	_____
SPEC RELOCATION OF EXISTING FIXED DOCKS	EA	4	_____	_____
SPEC ALLOWANCE FOR RELOCATION OF EXISTING WOODEN WALKWAY	LS	1	\$20,000.00	\$20,000.00
TOPSOIL FURNISHED AND PLACED	C.Y.	100	_____	_____
SEEDING AND MULCHING	S.Y.	278	_____	_____
TOTAL BASE BID AMOUNT				
ALTERNATE #1 - VINYL SHEET PILING				
SPEC VINYL SHEET PILING IN LIEU OF PRECAST CONCRETE	LF	450	_____	_____
(The unit price for seawall construction is to include the re-positioning of the existing rock, installation of un-graded Type A stone, ODOT Type D stone, ODOT Type #1, #2, and #57 stone as shown on drawings. Price shall also include all sheet piling, anchoring system, and trim).				

DOCK SUPPLIERS WHO HAVE BUILT TO ODNR SPECIFICATIONS

JANUARY, 2007

1. Atlantic-Meeco, Inc.
8262 Ninety Second St.
Alto, MI 49302
ATTN: Bob Strode
Phone: 616-891-7078
Fax: 616-891-7079
Cell: 616-450-6269
E-mail: rstrode_49333@yahoo.com
2. Galva-Foam Marine Industries
436 Sough State Hwy 7
Camdenton, MO 65020
ATTN: Mick Plemmons
Phone: 800-346-3323 or 573-346-3323
Fax: 573-346-4025
Cell: 573-216-3655
E-mail: mick.plemmons@shoremaster.com
3. Shore Master
PO Box 358
Fergus Falls, MN 56538
ATTN: Gary Haffley
Phone: 800-328-8945
Fax: 218-739-4008
Cell: 218-205-6412
E-mail: gary.haffley@shoremaster.com
4. Sullivan Flotation
P.O. Box 639
Warwick, NY 10990
ATTN: Steve Sullivan
Phone: 845-986-7377
Fax: 845-986-8531
E-mail: docks@sullfloat.com
5. O'Neill Marine Products
601 W. Cherry Street
North Baltimore, OH 45872
ATTN: Brian O'Neill or Skip
Phone: 419-425-4656
Fax: 419-425-1224
Email: brian@oneillmarine.com
skip@oneillmarine.com